



නියෝජ්‍ය ප්‍රධාන ලේකම් (ඉංජිනේරු සේවා) - දකුණු පළාත
 பிரதி பிரதம செயலாளர் (பொறியியல் சேவை) - தென் மாகாணம்
 Deputy Chief Secretary (Engineering Services) - Southern Province

දකුණු පළාත් ඉංජිනේරු සේවා කාර්යාලය - කොටුව, ගාල්ල.
 தென்மாகாணப் பொறியியல் சேவைக் காரியாலயம் - கோட்டை, காலி.
 Southern Provincial Engineering Services Office, Fort, Galle.

නියෝජ්‍ය ප්‍රධාන ලේකම් (ඉංජිනේරු සේවා)
 Deputy Chief Secretary (Engineering Service) : Tel/Fax: 091-2242786

විද්‍යුත් තැපෑල
 E-mail : gaks@sltnet.lk / info-eng@cs.spgov.lk

මගේ අංකය SPES/03/01/1-22/2020
 My No.

ඔබේ අංකය
 Your No.

දිනය
 Date

2020.10. 26

ප්‍රධාන ලේකම්,
 දකුණු පළාත.

2020 - I භාගයේ මිල ගණන් ඉදිරිපත් කිරීම.

2020 - වර්ෂයේ I භාගයේ ඉදිරිපත් කරන ලද මිල විශ්ලේෂණයේ මිල ගණන් කිහිපයක සංශෝධනයන් හා නව මිල ගණන් දකුණු පළාත් ප්‍රධාන ලේකම් කාර්යාලයේ වෙබ් අඩවියට ඇතුළත් කිරීමට කටයුතු කරන මෙන් කාරුණිකව ඉල්ලා සිටිමි. (සංශෝධනයන් හා නව මිල ගණන් මෙයට යා කර ඇත.)

ඉංජි. කේ.පී. වික්‍රමගේ.

නියෝජ්‍ය ප්‍රධාන ලේකම් (ඉංජිනේරු සේවා) බැ.බ.,
 දකුණු පළාත.

ඉංජි. කේ. පී. වික්‍රමගේ
 නියෝජ්‍ය ප්‍රධාන ලේකම් (ඉංජිනේරු සේවා) (බැ.බ.)
 දකුණු පළාත් ඉංජිනේරු සේවා කාර්යාලය
 කොටුව - ගාල්ල.

Rate Analysis for Construction & Repair Works - All
First Half 2020 - Southern Province - New Rates

Item Code	Description	Unit	Rate - LKR
<u>New Rates</u>			
Dm-33	Removing and stacking Aluminium partitions at site	m ²	227.00
EI -149	Supply and installation of 25 mm ² 4core Armoured cable CU/XLPE/SWA/PVC including excavation (0.45m x 0.7 x D)/ back filing/sand filing (0.2mx0.45m x D)/ (30mm*150mm*500mm) concrete tile bedding and all complete as per the instruction (ACL/Kelani/Sierra/Orrange)	m	6,012.00
EI -150	Supply and installation of 35 mm ² 4core Armoured cable CU/XLPE/SWA/PVC including excavation (0.45m x 0.7 x D)/ back filing/sand filing (0.2mx0.45m x D)/ (30mm*150mm*500mm) concrete tile bedding and all complete as per the instruction (ACL/Kelani/Sierra/Orrange)	m	6,900.00
EI -151	Supply and installation of 50 mm ² 4core Armoured cable CU/XLPE/SWA/PVC including excavation (0.45m x 0.7 x D)/ back filing/sand filing (0.2mx0.45m x D)/ (30mm*150mm*500mm) concrete tile bedding and all complete as per the instruction (ACL/Kelani/Sierra/Orrange)	m	8,789.00
EI -152	Supply and installation of 70 mm ² 4core Armoured cable CU/XLPE/SWA/PVC including excavation (0.6m x 0.7 x D)/ back filing/sand filing (0.2mx0.6m x D)/ (30mm*150mm*500mm) concrete tile bedding and all complete as per the instruction (ACL/Kelani/Sierra/Orrange)	m	11,728.00
EI -153	Supply and installation of 95 mm ² 4core Armoured cable CU/XLPE/SWA/PVC including excavation (0.6m x 0.7 x D)/ back filing/sand filing (0.2mx0.6m x D)/ (30mm*150mm*500mm) concrete tile bedding and all complete as per the instruction (ACL/Kelani/Sierra/Orrange)	m	15,340.00
EI -154	Supply and installation of 120 mm ² 4core Armoured cable CU/XLPE/SWA/PVC including excavation (0.6m x 0.7 x D)/ back filing/sand filing (0.2mx0.6m x D)/ (30mm*150mm*500mm) concrete tile bedding and all complete as per the instruction (ACL/Kelani/Sierra/Orrange)	m	18,173.00
EI -155	Supply and installation of 150 mm ² 4core Armoured cable CU/XLPE/SWA/PVC including excavation (0.6m x 0.7 x D)/ back filing/sand filing (0.2mx0.6m x D)/ (30mm*150mm*500mm) concrete tile bedding and all complete as per the instruction (ACL/Kelani/Sierra/Orrange)	m	22,173.00


Ro-13b	Approved Quality Corrugated Asbestos sheets hip roofing on imported timber frame 150 x 75 mm purling and wall plate 150 x 50 mm ridge , 150x50mm hip rafters ,100x50 mmrafters and 50 x 50mm beares supplied fixed complete (100 x 50 mm rafter fixed in 2'-6' C/C) -Ridging measured separately <i>(Including Preservation of timber is achieved by Vacuum Pressure Impregnation of the timber with preservatives, using the latest technology Such as CCB by BI Commodities & Logistics Pvt Ltd (certificate should be submitted)</i>	m ²	5,017.00
Ro-15b	Hip roof with Calicut pattern tiles on Imported sawn timber frame work complete with 150x50mm ridges, 150x50mm Hip rafters , 100x50mm rafters,150 x75 purlin and wall plate,50 x 25 reepers. rate to include tiling , ridging (bedded in cement and lime mortar 1:1:4, colour to match tiles)Truss Roof (Preservation of timber is achieved by Vacuum Pressure Impregnation of the timber with preservatives, using the latest technology Sush as CCB that are registered by register of pesticides for protection against wood destroying agents such as wood bores, fungi and termites (Execution according to the Manufacturers specifications)(BI Commodities & Logistics Pvt Ltd) certificate Should be submitted	m ²	6,046.00
Ro-35	Suppling calicut pattern flat tile class 1	nr	101.00
Ro-36	Suppling calicut pattern ridge tile class 1	nr	115.00
Pb-11 a	Mirror, bevelled, bath room type, oval shape ("Plastic")supplied and Fixed to wall with Rawl plugs (18"x24")	nr	2,451.00
Pb-62a	Supplying and fixing Soap tray (Nickel Apply)	nr	1,354.00
Pb-62b	Supplying and fixing Soap tray (Plastic)	nr	938.00
Pb-70	Supplied and fixed, PVC 1/2" Concealed valve" Water Tec" Chromium plated	nr	1,518.00
Pb-70 a	Supplied and fixed,1/2" Concealed valve "Water Tec"	nr	1,161.00
Pb-71	Supplied and fixed, Nickel flexible hose 450 mm long	nr	858.00
Pb-71a	Supplied and fixed, Nickel flexible hose 600 mm long	nr	908.00
Pb-71 b	Supplied and fixed, Nickel flexibal hose 900 mm long	nr	987.00
Pb-71c	Supplied and fixed, Plastic white flexible hose 450 mm long	nr	663.00

Pb-71d	Supplied and fixed, Plastic white flexible hose 600 mm long	nr	741.00
Pb-71 e	Supplied and fixed, Plastic white flexibal hose 900 mm long	nr	880.00
Pb-72	Supplied and fixed, 1/2" tank float valve plastic	nr	1,320.00
Pb-72a	Supplied and fixed, 3/4" tank float valve plastic	nr	1,664.00
Pb-72b	Supplied and fixed, 1" tank float valve plastic	nr	1,904.00
Pb-73	Supplied and fixed, tank ball valve 1/2" brass	nr	1,907.00
Pb-73a	Supplied and fixed, tank ball valve 3/4" brass	nr	2,474.00
Pb-73b	Supplied and fixed, tank ball valve 1" brass	nr	2,763.00
Pb-74	Supplying and fixing Door bend 110mm	nr	1,155.00
Pb-74a	Supplying and fixing Bend 110mm	nr	844.00
Pb-75	Supplying and fixing Door Tee 110mm	nr	1,300.00
Pb-75a	Supplying and fixing Equal Tee 110mm	nr	1,105.00
Pb-76	Supplying and fixing Door Y 110mm	nr	1,483.00
Pb-76a	Supplying and fixing single Y 110mm	nr	1,250.00
Tg- 01	12mm clear float tempered glass partition in ss u channel (304) including 37mm x 25mm top bar and 25mm x 25mm side and bottom bar with necessary 37mm s/s screws (csk head) 600mm c/c, rawl plug , mac rod (8mm) and binding sealer...etc	m ²	8,144.00
Tg- 02	12mm clear float tempered glass door,consisting with floor hinges (vvp) , Door handle , door lock and necessary accessories and riverts , screws... etc Rate to include for making flat shape as outer line	m ²	26,493.00

Prepared by :  **D.A.D. FERNANDO**
Engineering Assistant (SL TS-St:Class)
Southern Provincial Engineering Services Office
Fort - Galle.

Approved by :

Checked by : 


Director of building
Southern Province

Recommended By : 

Eng. K. P. WICKRAMAGE
Provincial Director (Buildings)
Engineering Services Office
Fort - Galle.

Eng. V. K. K. Juwanabadu
Chief Engineer (School Buildings)
Provincial Engineering Service Office
Fort - Galle.

Rate Analysis for Construction & Repair Works - All
First Half 2020 - Southern Province • *Corrected Rates*

Item Code	Description	Unit	Rate - LKR
	Corrected Rates *		
Dm-19	Removing and stacking partitions at site including making good to walls and floors (<i>Timber partition</i>)	m ²	855.00
Ro-30	Supplying .47 mm Zn/Al clour bonded roofing sheet(AZ150, 550Nmm ² Strength) with heat insulation system (16 kg/m ³ , 50 mm thk glass wool blanket sheet with 03 way reinforced Double sided Al foil on 75 x 75 GI mesh- gage 17) & roofing sheet fixing to existing "c" purling frame with No 12-14 x 55 mm fastners , GI mesh fied with No 12-14 x 20 mm fastners (Bluescope lysaght , metecno)	m ²	3,061.00
Ro-31	Supplying .47 mm Zn/Al clour bonded roofing sheet(AZ150, 550Nmm ² Strength) with heat insulation system (mack foil on 75 x 75 GI mesh- gage 17) & roofing sheet fixing to existing "c" purling frame with No 12-14 x 55 mm fastners , GI mesh fied with No 12-14 x 20 mm or No 12-14 x 25 fastners (roofing sheet Bluescope lysaght , metecno)	m ²	2,398.00
Pb-32	Pipes P. V. C. ½" supplied and fixed- PNT 14	m	291.00
Pb-33	Pipes P. V. C. ¾" supplied and fixed- PNT 11	m	403.00
Pb-34	Pipes P. V. C. 1" supplied and fixed - PNT 7	m	190.00
Pb-35	Pipes P. V. C. 1¼" supplied and fixed- PNT 7	m	384.00
Pb-36	Pipes P. V. C. 1½" supplied and fixed - PNT 7	m	454.00
Pb-37	Pipes P. V. C. 2" supplied and fixed - PNT 7	m	707.00
Pb-60	P.V.C. pipes 110 mm dia.(4") type 600 PNT7 laid under ground not exceeding 600 mm depth. Rate to include for necessary excavation, ct., Con. Bedding & covering with 1:3:6(1") con. Mixture. For special purpose only	m	3,124.00
Pb-62	Supplying and fixing Soap tray (Desigle, Rocell) IDC - AO222	nr	7,094.00

Prepared by : *D. P. Manawadu*

D. P. Manawadu
 Engineering Assistant
 (S.L.T.S. Sp. Class)

Southern Provincial Engineering Services Office
 Fort - Galle.

Approved by :

Checked by : *M. P. N. Gulawita*

M. P. N. Gulawita
 Engineering Assistant
 (S.L.T.S. Sp. Class)

Southern Provincial Engineering Services Office
 Fort - Galle.

Eng. K. P. Wickramage
 Director of building
 Southern Province

Recommended By : *Eng. V. K. K. Juwanabadu*

Eng. V. K. K. Juwanabadu
 Chief Engineer (School Buildings)
 Provincial Engineering Service Office
 Fort - Galle.

Eng. K. P. WICKRAMAGE
 Provincial Director (Buildings)
 Engineering Services Office
 Fort - Galle.